BOWS AND ARROWS: A CHAPTER IN THE EVOLUTION OF ARCHERY IN AMERICA

BY

PAUL E. KLOPSTEG

Professor Emeritus, Northwestern University

FROM THE SMITHSONIAN REPORT FOR 1962, PAGES 567–592
(WITH 5 PLATES)



(PUBLICATION 4565)

SMITHSONIAN INSTITUTION
WASHINGTON : 1963

MAIN
KANSAS CITY, MO. PUBLIC LIBRARY
0 0001 4574359 7
592+12=604

[illegible] ARROWS:
A Chapter in the Evolution of Archery in America

By PAUL E. KLOPSTEG
Professor Emeritus, Northwestern University

[With 5 plates]

This article, as a first objective, is intended to acquaint the reader with the sports and other pastimes which have to do with the bow and arrow. Among the pastimes, perhaps surprisingly, are the serious theoretical and experimental studies of these ancient implements, which contributed in large measure to the unparalleled increase in their use in this country during the past 30 years. As a second objective, an account of the technological advance which resulted from the studies seems worth presenting, since the development is interesting in its own right and because it is probably unique in sports history.

The sports mentioned are comprised of a variety of ways of using the bow, all of which depend on skillful handling. Other diversions include the collecting of old books and prints, which not only give insight into the practice of archery centuries ago, but also reveal something of the customs of those times. Then, too, there is the collecting of bows, arrows, and associated gear from around the world, and of artifacts which were obviously or presumably related to archery. For a person of my interests, the most interesting diversion, which attracted others of like tastes, is the research and development aimed at understanding the mechanics of propulsion of the arrow and of its flight characteristics.

It is not intended here to review the history of archery, for to do so would go far beyond the scope of this article. For reasons already mentioned, the technical side of archery will be treated more fully than the others. It is the area to which my attention and interest were initially attracted, and the area in which the rapid evolution of archery in the United States took place.

KANSAS CITY (MO.) PUBLIC LIBRARY
6604231

My immersion in archery began in the late 1920's, when a dormant interest in the flight of a projectile was fanned to activity by my undertaking, one summer, to do target practice with arrows. During World War I my work had been largely in experimental ballistics. This may have stimulated a desire to know more about the manner of flight of the arrow, about the way in which energy is stored in the bow, and about the mechanism of transfer of the stored energy to the arrow—in short, about the physics of bows and arrows. One of the chief attractions of archery is the opportunity of applying the findings of science and engineering to the design and construction of bows and arrows.

Because of its venerable age and traditions, a voluminous literature has grown up in archery, especially in English. Less well known in English-speaking countries is the wealth of written records concerning archery in Arabic, Chinese, Persian, Turkish, and other oriental languages. By contrast, little of such writing has been produced in German or French. The collecting of old books and prints and more ephemeral items as well is a possibility not easily matched in any other sport. Its antiquity, its unique role in the history of nations, its science and technology, and its appeal to craftsmanship—the combination of all these is rarely found outside of archery.

Competent estimates indicate that 6 million or more persons in the United States are serious about some form of archery. To discover reasons for such wide appeal, observe that the bow is one of the first if not *the* first of propellant devices invented by man. To what epoch in prehistory its genesis may be assigned is not clearly established, but that game was hunted with the bow many millenniums ago is attested by the rock paintings in the Cueva de los Caballos in eastern Spain. Among prehistoric tribes the bow was the steadfast companion of the family provider, of the group defender, perhaps even of the tribal aggressor. Without doubt it was the principal implement used in the struggle for existence. To this day it plays the same indispensable role among primitive tribes of Africa and South America.

The bow is thus an authentic antique. Its antiquity, along with the fact that the modern bow and arrow are in principle unchanged from their prototypes, invests their use with fascination among sports which employ specialized instruments. Appreciation of this and other attractive attributes helps in part to explain its growth and present large number of followers. Archery has always been more a participant sport than a spectator's, which makes its phenomenal expansion all the more noteworthy. Its number of followers will always remain small in comparison with the crowds who are baseball and football enthusiasts.

Among the diversions which comprise the "world of sports" one comparison is the relative market for the implements used. By this test a participant sport ranks high, for nearly everyone interested in it is a potential buyer for its equipment. Archery, so measured, has arrived as a major sport. Its manufacturers and suppliers are found among the larger business enterprises. Manufacturers of firearms and fishing tackle have entered the primary market. One other indicator which confirms its rank is the rapid expansion of its specialized magazines, the number of recently published books, and the avid collection of old books and other material published in the field.

FIGURE 1.—An English longbow of the 1850's, unstrung. The upper limb, 34" long, is at the left, the lower limb, 34" long, at the right. To provide better grasp, the grip is enlarged by a shaped pad of cork glued to the back of the bow. The bow is made of two strips of wood glued together. The back is probably lancewood; the belly is a dark, hard wood, unidentified, but possibly degame, stained deep brown.

Today's number of archers contrasts sharply with that of only 30 years ago. During this period there has probably been a doubling of numbers every 5 years, which would make the ratio more than 60/1, which seems plausible. Prior to 1930, the number of archers in America was almost too small to be noticed. In the tables of data about outdoor sports, its category was "miscellaneous" or "other." Seldom did the public press carry news about it. Among the reasons for the prevailing popularity of the sport, a major one to be examined is the exceptional improvement of its implements. This new excellence was the first in centuries, the centuries during which makers of bows and arrows blindly and uncritically followed tradition.

Though unchanged in principle, the instruments of archery today differ profoundly in detail from their prehistoric and historic prototypes. They differ radically even from the more recent ones being used during the first few decades of this century. Changes in design, materials, and construction have contributed incomparably to precision in performance, hence to greater accuracy in the hands of the skillful user. Even the fantastic skill attributed to Robin Hood and his outlaws of Sherwood Forest does not surpass that of many of our present-day bowmen. The new designs have undoubtedly served as a potent catalyst both in stirring the latent interest of many potential archers, and in stimulating manufacture of the new bows which, unlike the old, lend themselves to systematic mass production.

Shooting an arrow at a mark such as the bullseye or "gold" of a standard target has much resemblance to measuring a physical constant with the purpose of determining its value to the utmost attainable accuracy. To increase the accuracy in such a measurement,

the first requisite is precision made possible by the use of instruments of greater sophistication. In shooting, these instruments are the bow and arrow which in their present design and construction are indeed sophisticated. To attain maximum precision with them requires:

1. Minimum differences, in successive shots, in the energy stored in the bow at equal lengths of draw.

2. Minimum effects of temperature and humidity on the materials of which the bow and the arrows are made.

3. Minimum differences in dimensions, materials, and shapes of the arrows comprising the set.

4. Arrows of proper spine in relation to the bow. (Spine is a characteristic of an arrow which depends on such factors as stiffness, resilience, mass, and distribution of mass along the shaft.)

5. Exact replication by the archer of all the sequences of action in the process of shooting, i.e., of drawing the bow and "loosing" the arrow.

Requirement 5, which calls for near perfection in the archer's coordination and in the execution of the difficult, interrelated steps in the shooting of an arrow, is to an extent dependent on the other specifications enumerated. His confidence in his ability to perform all the necessary actions properly is increased if he can be sure that these specifications are closely met.



FIGURE 2.—The bow of Figure 1, strung ("braced") for shooting.

In the United States the bow and arrow are used in five main categories of the overall sport. The oldest form, widely practiced, derives from the kind of target shooting long practiced in England. It consists of competitive rounds, variously named, such as York, American, National. Each round consists of certain numbers of "ends" of six arrows each, at several known distances. The York Round, for example, calls for 12 ends at 100 yards, 8 at 80 yards, and 4 at 60 yards for a total of 144 shots. The standard target on a thick straw mat is 4 feet in diameter. Its gold bullseye is 0.8 foot in diameter. This is surrounded by four concentric rings each 0.4 foot in width, having colors red, blue, black, and white going outward from the gold. A hit in the gold counts 9; and the rings, going outward, have values of 7, 5, 3, and 1, respectively.

Clout and wand shooting are variations of the customary rounds. In the former, a target 12 times the diameter of the standard, namely, 48 feet, is laid out on the turf, with its center 180 yards from the shooting line. The arrows are loosed at a high initial angle and come

down steeply to stick in the sod on which the target is described. In wand shooting, a vertical lath 2 inches wide is set up at 100 yards, and hits are counted regardless of their elevation on the wand.

A second category called flight shooting puts a premium on skill in shooting for maximum distance. The bows and arrows are especially designed for the purpose. Another, field archery, requires a course of 14 targets, laid out where possible up hill and down dale, with distances only approximately known, and with targets roughly proportional in diameter to the distances from the shooting stands. Hilly woodland is preferred terrain, with natural hazards, or with artificial ones built in.

Still another bow-and-arrow sport is archery golf, played on a golf course. Bows and arrows are substituted for clubs and balls, and the cup is replaced by a circular disk of the same diameter as the cup, supported vertically. Some historians of sport surmise that the "antient and honourable game" of golf is descended from the old archery game of rovers. In this form of contest the participants, ambling about the countryside, selected a series of marks as they strolled, and scored the total number of shots to hit the marks, low score winning. Archery golf may, in fact, be "rovers reviv'd," in modified form.

The fifth major category, and the one growing most rapidly, is that of hunting wild game with bow and arrow. Most States have long open seasons limited to bow hunting, usually preceding the rifle hunting season for deer. Deer hunting is the most popular version. Hundreds of deer fall annually to the bow, but this is only a small fraction of those still being taken each year with rifles. The word "still" is used by design, because many of today's bow hunters are yesterday's riflemen. Other large game being hunted with the bow includes bobcats, mountain lions, javelina, elk, and moose in this country, as well as black and brown bears. Rabbits, squirrels, and upland birds are among the small game. Carp and gar fishing with the bow and special arrows is becoming increasingly popular.

The requirements for precision shooting where the object is to hit a mark have already been enumerated. These are closely approximated in most modern bows and arrows. Thus any appreciable scatter on a target of six matched arrows may be attributed to the archer's technique, to the variations in his performance in the different shots. Variable and gusty winds increase the scatter, whereas in a steady wind, the effect can be minimized by allowing for drift. With all these factors considered, it seems reasonable to use the comparison of scores of today's champion archers with the corresponding scores of 35 years ago as a measure of improvement in the equipment during the intervening period. Before the improved bows and arrows were

672-174—63——42

available, it was standard procedure for the archer who was striving for highest score to shoot his matched arrows repeatedly with a given bow, to determine their dispersion pattern, and to fix in his mind the deviation of each arrow, identified by number, from the intended point of impact at various target distances. He also needed to know the effects of temperature and humidity on the performance of his tackle, and make due allowances for them. With these precautions, experts could make fair scores.

The story of how bows and arrows became the objects of study by scientists and engineers, and how the transformation in design from the old to the new came about, begins in the 1920's.

Among those who became the pioneers in studies looking toward improvement, C. N. Hickman is one of the leaders. His training in physics to the doctorate was at Clark University, where he worked with Robert H. Goddard, known as the father of modern rocketry. Soon after the first World War, Hickman was employed at the National Bureau of Standards and soon thereafter transferred to the Washington Navy Yard as research engineer. He seems to have inherited his interest in archery. His grandfather learned it from the Indians, and his father was one of the relatively small number of archers in the United States during the last decade of the 19th and the early decades of the 20th centuries. Throughout his career Hickman has been a confirmed experimentalist in mechanics, with specific and practical objectives, and with exceptional ingenuity in devising and constructing apparatus and systems needed for specialized measurements and mechanical performance.

His exploration of the mechanics of the bow included the design and construction of a shooting machine with which hand shooting could be more closely simulated than in earlier machines of this kind. In it he employed a nonjarring pneumatic release, adapted from the pneumatic bellows used in a player piano. The device makes possible the reduction to minimum of the inevitable small variations in the process of shooting by hand. The machine and his modified form of the Aberdeen Chronograph, on the development of which I was engaged at Aberdeen Proving Ground and in Philadelphia during World War I, made it feasible to measure accurately the short time intervals involved in determining velocities and accelerations of arrows being discharged from bows. Data could thus be obtained for better understanding of the "interior ballistics" of the bow and arrow combination, and of the velocities and retardations involved in the "exterior ballistics" of the missile.

The beginning of my interest in these matters in the summer of 1929 came about through the fact that part of the family's vacation pastime was provided by a beginner's archery set and a homemade target.

First efforts sought to gain skill and improve scores. Practice was guided by an instruction sheet which came with the set. We started with complete ignorance of the techniques, so that improvement began from the zero level. In the course of my self-instruction in the art of "shooting in the bow" my familiarity with physics helped me to recognize the mechanical principles and problems involved in the propulsion of an arrow by means of a bow.

To increase the success of our efforts I bought and read what few up-to-date books on archery could be procured, and subscribed to the single archery magazine then being published, "yclept 'Ye Sylvan Archer' "—the title of which provided a flavor of romantic antiquity and old tradition for a struggling journal by and for amateurs.

The appearance of some of Hickman's articles in this magazine led to a renewal of our acquaintance. A lively correspondence about the physics and engineering aspects of archery developed. My Aberdeen Chronograph and shop equipment became the nucleus of an attic laboratory for which I built a shooting machine and other specialized apparatus. The latter included high-speed flash equipment for obtaining instantaneous photographs of an arrow being accelerated by the bow, and measurement of force-draw characteristics of a bow by photography. I was thus launched, not to say propelled, into experimental studies which were all the more welcome for the diversion they afforded from the serious economic problems following the great depression of 1929. In many respects, my equipment was similar to Hickman's, so that we could easily compare and check measurements and keep our efforts cooperative and complementary.

My publications reporting on these experiments began in 1931, first in "Ye Sylvan Archer," and later in a newly established journal of small circulation, the "Archery Review." Reference to the bibliography shows that several engineer-scientists other than Hickman and myself also published several papers, a few of which appeared in the Journal of the Franklin Institute. Among the authors were English, Higgins, Nagler, and Rheingans.

The topics listed below give a picture of some of the interesting problems with which the research and development efforts dealt; but many questions were only partially answered. There is still plenty of rewarding pastime left in them for anyone who feels inclined to apply his skill to their solution.

1. The effects of the shape, dimensions, relative settings, and angles of limbs on the static force-draw relation as the bow is drawn and the dynamic force-displacement relation as the arrow is accelerated.

2. The static energy-draw relation as the bow is drawn.

3. The velocity of departure of the arrow and its kinetic energy derived from the energy in the drawn bow.

4. The mass-velocity relationship and corresponding mass-energy relationship for arrows of different masses shot from the same bow.

5. Effect of the mass of the string on the initial velocity and energy of the arrow.

6. The efficiency of a bow-arrow combination, i.e., the fraction of the stored energy in the bow which appears as kinetic energy in the arrow.

7. The "virtual mass" of the bow.

8. Factors which affect performance of arrows: their effects on accuracy, and consistency and distance in flight.

9. The geometry and methods of aiming.

10. Psychological factors in shooting.

The list above is representative of some of the questions in the mind of the observant, analytically minded archer who has serious inclinations toward finding the answers. If he does, he has potential guides to improvement in performance of both the archer and his implements, and the search for the answers will have provided pleasant avocation for those who enjoy such pursuits. Our discussion of these matters will be illustrative rather than exhaustive.

Known kinds of bows are numerous. They may have long limbs or short limbs, equal or unequal in length. Cross-sectional shapes of the limbs are various. Materials may be wood, of a single kind, in "self" bows, or of different kinds, glued together in layers. There are "composite" bows, with layers of several kinds of organic materials, or, in modern form, of laminae of wood and synthetic plastics reinforced with fiberglass.

The two representative types of bow from which the kind now generally used has evolved are the longbow, with which are associated centuries of history and tradition, and the oriental, specifically the Turkish, composite bow. Prototypes of the latter are the bows used by the Saracens and by the conquering hordes of Genghis Khan. We have authentic information, dating back to the 15th century, about the Turkish bow. Through the following centuries its design apparently never changed. In the middle of the 19th century, interest in archery vanished with the end of the reign of Sultan Mahmud II, and few if any bows were made in Turkey thereafter.

The English longbow had straight limbs when relaxed, i.e., not strung, except as the limbs might have taken a set from having been repeatedly drawn. The limbs terminated in fitted tips of horn with grooves ("nocks") in which the loops of the string were seated. Limbs tapered in both width and thickness from grip to tip. At any cross section, the limb was rounded on the belly side, toward the string, and more or less flattened on the back, on the opposite side. In the drawn bow the belly is under compression, the back under ten-

sion. Several shapes of cross section are shown in figure 3. Such a limb is said to be stacked.

The grip occupied the region where the tapering limbs merged, and bending occurred throughout the length of the bow. For this and perhaps other reasons, an unpleasant recoil might be felt in the bow hand when the arrow was loosed. The stacked limb, characteristic of the longbow, was a violation of good mechanical principles and did not properly exploit the possibilities of the wood from which the bow was fashioned. On the contrary, it subjected the wood to needlessly high stresses. Indeed, such a bow had to be long to minimize stresses and prevent breakage; hence *long*bow. That the margin of safety in the longbow was recognized as precarious is implied in the saying that a bow fully drawn is nine-tenths broken. This is not true of the modern bow. Another feature of the longbow was that its lower limb was about 2 inches shorter, and stiffer, than the upper. This seems to have been a concession to the bowyer's desire to keep the overall length within tolerable limits and to have the arrow engage the string at the midpoint of the latter. Both desires were satisfied by moving the handgrip in the direction of the lower limb by a couple of inches.



FIGURE 3.—Typical shapes of cross sections of limbs of traditional longbows.

During the known history of the longbow up to the early 1930's the only change in design seems to have been one intended to reduce the aforementioned recoil in the bow hand. The change consisted of making the grip rigid and nonbending by leaving more wood in the handle portion. The limbs then, instead of merging within the grip, made juncture somewhat abruptly with the heavier midsection, where the latter was fashioned into dips which merged into the limbs. The limbs thus became more clearly defined in length. In other respects the design remained frozen.

The original motive for Hickman's work and mine was the conviction, bred by recognition of the theoretical shortcomings of the longbow and by the desire to improve its performance, that much better bows could be made. The improvements that resulted from the work demonstrate the effectiveness of using science and engineering principles as compared with the stagnation inevitable in adherence to tradition. In contrast with these improvements, brought about within a few years, is the frozen design to which bowyers in England and America adhered through the centuries, because they "knew" that it



FIGURE 4.—Schematic side view of a bent limb. The dotted line indicates location of the neutral layer.

could not be improved. They must have felt certain that any attempts to improve their product were predestined to failure. I have recollections of pre-1930 bowyers speaking with pride, if not boastfully, of their ability in selecting yew wood for making bows par excellence. But no matter how singularly excellent the quality of the wood they selected, or how well it was seasoned, even the best of their bows required a high initial angle of trajectory for the arrow to hit the target at 100 yards. This did not contribute to high scores, nothwithstanding their derogation of the higher velocity and flatter trajectory of the new bows, not attainable with theirs.

It may interest the reader to follow the major steps by which the improvements were achieved. Our point of departure was the longbow, as used in this country prior to the early 1930's which was the English pattern modified with the rigid grip.

Mechanics, that section of physics which deals with static and dynamic forces, with kinematics, and with the properties of materials subjected to stresses, shows that when a elastic beam is bent, it is under tension which causes stretching on the convex side and under compression, causing shortening on the concave side. Somewhere between there is a geometric "layer" of zero thickness which neither stretches nor shortens as the beam is bent. At this "neutral" layer the shearing force between the stretched and the compressed sections is a maximum, and this diminishes to zero as we move outward, at right angles, to the surfaces of the beam.

To illustrate this, consider the limb of a longbow (fig. 4). A force F_s applied to the tip through the string causes the limb to bend in a curve which depends on the force, and on the shape, dimensions, and elastic properties of the limb. At any section AB within some finite radius of curvature, the tensile force is F_t and the compressive force F_c. These forces increase from zero to maximum values as we go outward from the neutral layer. The bending moment at the section is the summation of the tensile and compressive forces over the elements of area on each side of the neutral layer, giving a resultant tensile and compressive force, respectively; the sum of each of these resultant forces, multiplied by the distance of its point of application from the neutral axis of the section, is the bending moment at the section. This is equal to the moment represented by the force along the string multiplied by the perpendicular distance of the section AB from the string: $F_s \times d_{AB}$.

Figure 5 represents a section AB of the limb in figure 4, of a typical longbow. Line CD through the center of mass of the section is the neutral axis. The neutral axes of all the sections define the neutral layer; conversely, the neutral layer contains all the neutral axes of all possible sections. In the section shown, the distance from the neutral axis to the outer surface of the back of the limb is less than the cor-



FIGURE 5.—(a) Section of a stacked limb. CD is the neutral axis, containing CM, the center of mass of the section. (b) Force diagram at this section of the stressed limb showing proportionality of fiber stress and distance from the neutral axis.

responding distance to the outer surface of the belly. Since the maximum tension and compression occur at the outer surfaces, the back is subject to lower maximum stress in tension than is the belly in compression. It is a general characteristic of wood, both from the standpoint of intrinsic strength and of imperfections, that it can withstand greater tension than compression without failure. Thus, in a stacked limb, forces to which the wood is subjected are not matched with the strength characteristics of the wood. This confirms the previous statement that in the longbow the qualities of the wood are not properly exploited. From mechanical considerations it would be better to reverse the shape of the limb, so as to make the stacked side the back and the flat side the belly. It is now evident why the longbow must be long to withstand the stresses to which it is subjected in use.

In a working bow, made of wood with suitable elastic properties, the energy in the bent limbs resides in the stresses set up in them as the bow is drawn. When the arrow is loosed, the wood tends to spring back toward its unstressed configuration. The best use of the wood or other resilient material is made when the maximum tensile and compressive forces are constant throughout the length of the limbs, with constant bending moment per unit area at any section. The condition can be approximated in a limb of uniform thickness, rectangular in section, bending in a circular arc. In handbooks of engineering one finds that a cantilever beam of uniform thickness, tapering from finite width at the point of support to zero width at its free end, with loading at the end, bends in a circular arc with light loading and small deflection. Hickman pointed out this simple fact and suggested that a bow with limbs rectangular in section, of uniform thickness and taper, would more effectively utilize the resilient qualities of the wood than does the longbow. Experiments carried on by Hick-



FIGURE 6.—Graphic method of designing a bow. BT, the limb, is divided into ten equal sections. Its tip, in bending, follows the path TT′, a circular arc with center at R and radius *t*, which is 3/4 BT in length. The length of the arrow is EP; the line CA represents the string on the braced bow, with CP the "bracing height"; ET′ represents the string at full draw. Arc BT′ represents the bent limb, with radius *r*, the center of which is located by the intersection of the line BF which is perpendicular to BT, and the perpendicular bisector of chord BT′. Perpendiculars to ET′ are dropped from each of the ten equally spaced points B, G′, H′, ... Q′, along the bent limb. The lengths of the perpendiculars are proportional to the respective widths of the limb at each of the ten locations.

man and myself some 30 years ago fully substantiated the point. When the deflection is large, as in a fully drawn bow, the bending moment per unit area is no longer uniform along the limbs. To restore uniformity, widths at different points along the limbs must be corrected so as to bring about the desired result of keeping the bending moment per unit area constant.

Figure 6 depicts a graphic method for determining the correct widths, along its length, for a limb of uniform thickness, to achieve the stated objective. Accordingly, it becomes the basis for the design of a bow with limbs rectangular in section, uniformly stressed.

Hickman showed that when a limb is bent in a circular arc, the path of its tip closely follows a circle having a radius three-fourths the length of the limb, its center being on the limb. This simple construction enables one to draw a circular arc representing the bent limb for any length of draw. The procedure for determining the

relative widths, in terms of the maximum width of the limb at its base, is described in the caption for figure 6.

It is of course impracticable to reduce the width of the limb to zero at the tip. This would have no place for seating ("nocking") the string, and because of the small width, the outermost several inches of the limb would be unstable and tend to twist. Accordingly, in constructing the limb, sufficient width is left in the outermost 3 or 4 inches to provide for a suitable nock and retain stability. To compensate for the extra stiffness due to the added width, the thickness of the end of the limb is reduced so as to approximate bending in this section on the same radius with the rest of the limb. The approximation cannot be close, because of the very small bending moment near the tip. The corners of the limb are chamfered to reduce concentration of stresses.

The new design, shown in plate 3, which in effect loads the limbs uniformly and thus makes optimum use of their elastic properties, made possible a reduction in their length by 10 to 15 percent, while reducing hazard of breakage. A dividend was the possibility of making the limbs of equal length, instead of keeping the lower limb 2 inches shorter than the upper, as in the longbow. This is accomplished by lengthening the rigid middle section sufficiently to provide the same length of rigid section above the arrow as there is in the handle section below the arrow, thereby keeping the bow symmetrical with respect to the axis of the arrow, with the arrow nocked at the midpoint of the string. Both limbs are now alike in dimensions and stiffness. Such a limb has a period of vibration much shorter than that of the equivalent limb of a longbow, the comparison between the two bows being based on their exerting the same static force on the arrow at full draw. The new limbs therefore spring back faster, impart higher velocity to a given arrow, and thus have greater efficiency in transferring their energy to the arrow.

Experiments with bows developed along these lines proved them to be far superior in efficiency to the longbow. Whereas the latter at best transferred 40 percent of its stored energy to the arrow, the new bows, according to measurement made both by Hickman and myself, had above 75 percent. With efficiency about double that of the longbow, it can impart an initial velocity to a given arrow about 40 percent higher than that produced by a longbow.

It seems appropriate at this point to quote from a letter which I received from a distinguished scientist and friend in Washington after I had sent him one of the new bows. He had been finding welcome relief from strenuous responsibilities in military research and development by practicing archery occasionally with the Potomac Archers, where he used a longbow. Upon receipt of the new bow, he tried it, then sent me the following comment:

> That is the doggondest bow I ever saw—and apparently that the Potomac Archers ever saw. I took it down yesterday. The club was having an informal

shoot so I snuck off on the side, nocked an arrow, picked a point of aim somewhat nearer than with the older bow, and let er go. I haven't seen that arrow since. I just hope it didn't plug someone. . . . When the gang started shooting at 100 yards, Mr. ———— joined me and helped me try it out. . . . He was drawing only 26 inches, so was losing a lot. But his point of aim at 100 was somewhere about the 40 yard line. He shot a couple, and it pretty well broke up the shoot because the gang gathered around as soon as they saw the flat trajectory. . . .

Publication in the early 1930's of a series of articles on the design and performance of the new bow met with some skepticism by tradition-bound archers, but it also met with widely increasing acceptance. As more archers acquired bows of the new design they were able to verify the published statements about performance. It took only a relatively few years for the longbow virtually to disappear from tournament shooting lines.

In parallel with the acceptance of the bow of scientific design, another circumstance strongly influenced the continuing improvement of bows. In the early 1930's I had begun to make a collection of books on archery, most of which are of English origin, published from the 16th century onward. Among the items in the collection is a complete run of an annual review volume called "The Archer's Register," beginning in 1864 and continuing through 1915. Some of these contained seemingly authentic information as well as some conjecture about the practice of archery in Turkey in the 15th and later centuries. One assertion was the almost incredible one that the Turks had shot arrows a distance of a half mile—incredible, certainly, to those who knew only the limited range of the longbow. My technical interest stirred me to discover whether this might be true, and if so, how it had been accomplished.

In my exploration of Turkish archery, I was fortunate in being able to obtain a book by Mustafa Kani, printed in old Turkish with Arabic-Persian calligraphy, published in Constantinople in 1847, and bearing the title, "Excerpts from the Writings of the Archers." Among the things reported was the construction and methods of shooting the Turkish bow.

Because of my inability to read Turkish, it was fortunate that I later discovered two other publications concerning Turkish bows and arrows, both based almost wholly on the book by Kani. The first was a paper entitled "Concerning Bows and Arrows: Their Use and Construction by the Arabs and Turks," by Dr. Freiherr Hammar-Purgstall, presented before the Imperial Academy of Sciences of Austria-Hungary and published in the proceedings of the Academy. The second, "Bowyery and Archery among the Osmanli Turks," by Joachim Hein, was published serially in three successive issues in 1921–22 of the German periodical "Der Islam." These two sources, both in German, which I read easily, were of substantial help in giving

FIGURE 7.—A Turkish archer, early 19th century, holding a composite bow at full draw, ready for loosing a flight arrow. Note that the arrow is drawn several inches within the bow, its tip resting in a guide (siper) strapped to the bow hand. (From "Turkish Archery and the Composite Bow".)

me insight into Kani's book, which otherwise would have remained obscure.

The result of the study of these two works led to my publishing a book in 1934, with the title "Turkish Archery and the Composite Bow." In it I reported what I had learned from the two German sources, along with comments and explanations deriving from both my practical experience in shooting, and from the research and development I had done. The book, published in a limited edition, proved to be in greater demand than had been anticipated, with the result that it became a collector's item on the day of its publication. A revised and enlarged edition was published in 1947, the centennial year of publication of the book by Mustafa Kani. The book deals exclusively with the Turkish bow, arrows, shooting accessories, methods of practice and of shooting, distance records and other related and pertinent information.

The Turkish composite bow differed profoundly from its English contemporary counterpart. Whereas the longbow was made exclusively of wood, the Turkish bow was "composite," with limbs constructed of materials in layers, so arranged that the compression, tension, and shear in the bent limbs occurred in those materials best adapted to withstand these respective forces. The precise form and construction of the composite bow must have evolved through experience in the use of the weapon, and from the trial-and-error method in construction employed by many successive generations of cooperating bowyers and archers.

The studies of Turkish bows and arrows, and their use in distance shooting, reported in the book on Turkish archery, left no doubt that their record distances were very much greater than any which had been achieved with the longbow. The principal reasons for the superiority were probably:

1. The greater energy storage per unit volume in the stressed limbs of the composite bow, made possible by the judicious use of suitable materials, and the geometry of the bow.

2. The design characteristics of the Turkish bow, such as shorter limbs, strongly reflexed when relaxed; and the setback, or "ears" at the ends of the limbs.

3. The design of the Turkish flight arrow, light yet strong and rigid to avoid buckling under high thrust; stabilizing vanes made as small as feasible, to minimize drag.

4. The use of a relatively short arrow, also designed to reduce drag, drawn several inches within the bow, made possible by the use of a special guiding device worn on the bow hand.

5. The thumb release, to minimize violent bending and deflection of the arrow during and immediately after release.

Many of the American archers interested in flight shooting who

had access to the book on Turkish archery realized the challenge which confronted them in the Turkish records, and proceeded to work at closing the wide gap between those records and the much shorter distances attainable with the longbow, or straight self bow of wood. Prior to publication of the book, some of them had already made changes in the longbow. They used limbs of rectangular section, shortened them to the limit of safety, and provided them with ears. This was the beginning of progress. The wood most frequently used in making flight bows was osage orange, a very strong, hard, resilient North American wood, named bois d'arc by the French explorers because they found it being used by many Indian tribes for bows. Seasoned osage orange wood of good quality has mechanical properties approximating those of horn, making the use of the latter as compression material unnecessary. Sinew fiber was, however, used for backing, to safeguard the limbs against breakage from possible flaws in the wood, and to withstand the high tensile stress which develops in a bend of short radius. They had learned from the book how the Turkish craftsman prepared the sinew and glue, and how he applied the sinew fiber, in a glue matrix, to the bow. With such transitional models of bows, flight distances increased through the 400's of yards into the low 500's.

Research and development during and since the war produced plastics with excellent characteristics for reliably storing and releasing energy through stress loading and unloading. Mass production at low cost of glass fibers was perfected, making long parallel fibers of glass readily available. Strong plastics with fiber glass reinforcement are now in regular if not exclusive use in the construction of bows of all kinds. Except in certain kinds of specialized, custom-built bows, sinew fiber, horn, and osage orange wood have been displaced by the new materials. The bow of the 1960's is composite in the Turkish tradition, though in modified pattern, influenced by the designs which developed from the research studies of the longbow.

Plates 4 and 5 represent one commercial form of modern bow, relaxed, braced, and at full draw. Although resemblance to the Turkish bow is manifest both in appearance and its composite structure, the straight-limbed bow of rectangular limb section had a strong influence upon its development also, as an intermediate phase after the longbow. The limbs are rectangular in section, with adequate width to insure stability against twisting as the bow is drawn. Moreover, the design is aimed at employing the whole limb, including the backwardly curved ends, for storing energy. The lesson learned from the bow with rectangular limb section, bending in circular arcs, is that each limb is "working" throughout, with approximately the same stored energy in each unit of volume of the stressed limb. In the Turkish bow only about one-half the length of each limb is under great stress when the bow is drawn. In the modern bow, which is

composite as is the Turkish, the tensile stress is taken by glass fibers in a matrix of strong plastic, and the compressive stresses by the plastic, perhaps aided by the glass fibers embedded in and bonded to it. The limb is built upon a thin strip of wood, usually hard maple, to both sides of which the plastic with embedded glass fibers is bonded. The limb of the Turkish composite bow was constructed similarly, but, it will be recalled, with horn to take the compression and sinew fibers to take the tension.

One of the outstanding gains of the new construction as compared with that of its precursor, the wood bow with rectangular-section limbs, is the relative immunity to normal temperature and humidity variations. Moreover, the modern composite has little or no tendency to follow the string, i.e., to take a permanent set from being braced and drawn. It may be left braced over long periods, and when relaxed, will resume its original form. A significant test of such a bow was to draw it full and let it snap 260,000 times. After this "abuse" the force at full draw was the same, within a few ounces, as it was when new.

The modern bow has the long rigid midsection which has been mentioned before. It permits using short limbs of equal length, and application of the drawing force to the bow along a line approximating the axis of the arrow as an axis of symmetry. A new feature is the sculptured grip, as seen in plates 4 and 5, shaped not only to fit the contours of the hand, but also to make certain that the force applied by the bow hand is always applied at the same location. An arrow rest, and a marked nocking point on the string insure the proper positioning of every arrow and replication in each shot of the impulse applied to the arrow. These features minimize variations which would introduce inaccuracies in hits. Another important characteristic which makes a similar contribution to accuracy is the absence of energy loss in the limbs from mechanical hysteresis, or internal friction in the materials of the limbs. This is present in most self bows of wood. It is related to permanent set in the limbs, which has been previously discussed.

The modern arrow also makes its contribution to accuracy. For the most part, precision arrows are now made of strong aluminum alloy tubing, precision drawn, with constant physical properties such as stiffness and mass per unit length for each diameter and wall thickness. The wood arrows, which have been largely superseded, suffered from the inevitable lack of homogeneity of wood. Notwithstanding close attention to manufacture, meticulous selection and seasoning of wood, and other handling intended to increase uniformity, complete identity of specifications for every arrow in a dozen could only be approximated. The final step in matching the arrows in a dozen

was that of selection, through measurements and tests, from a large number.

Another point of importance in accurate shooting at long distances, such as 100 yards in the York Round, is that the drag on the arrow must be alike for all. The principal cause of variation in drag has been in the vanes made of turkey feathers, which are easily disarranged or damaged by mechanical impact, and changed in texture and uniformity when wet. In the new designs, plastic vanes are used, with the result that greater uniformity is achieved with smaller effort. Some experimenters and manufacturers have used four or six vanes in place of the usual three. The only advantage is that for the same area of stabilizing surface, the larger number may be made somewhat narrower, and this may have value in preventing contact of the vanes with the bow when the arrow is loosed.

The drastic changes made in bows and arrows during the three decades past have produced emotional reactions among the older archers to whom the legend of Robin Hood was sacrosanct, and who were unable to tolerate innovation. They lived in the old English tradition with the longbow and the arrows made of "old deal." They ridiculed the research and development which pointed the way to better shooting and higher scores. Clearly they were entitled to hold affectionately to the Robin Hood image of archery. However, their predictions about the decline of archery, caused by the newfangled gear, failed of fulfillment. The number of archers has moved from the thousands into the millions. In large part this has come about by leaving tradition behind. The new bows and arrows have added immeasurably to the potential enjoyment of the sport.

A brief compilation of some of the technical considerations involved in the advancement of the art will, I hope, interest many readers, for it helps in following the rationale of the research and development which have been described.

The force-draw relation.—The most obvious characteristic of any bow is the relation between the force and the displacement of the nocking point of the arrow on the string. In graphic form, the relation is expressed as the force-draw curve. It shows the force exerted by the bow on the arrow at any point of the path in which it experiences acceleration.

In figure 8 are shown force-draw curves of bows of the several kinds which are under discussion in this report. These are adjusted to the same maximum force of draw at the same length of draw.

The significance of the force-draw curve in these studies is the fact that from it one obtains the energy in the drawn bow. The measure of the energy is the area enclosed by the graph, the X-axis at zero force and the ordinate at maximum force. The force-draw



FIGURE 8.—A group of force-draw curves for bows of different types. (1) A short bow with straight limbs; (2) a longbow; (3) a straight-limbed short bow with backwardly curved tips (ears); (4) a modern composite bow, as shown in pl. 5; (5) a Turkish composite bow as shown in pl. 2, *d*.

curve for the longbow approximates a straight line. For a short, straight-limbed bow it curves slightly downward from that for the longbow. Backwardly curved tips produce convexity upward, as do strongly reflexed limbs of the kind employed in the Turkish bow, and some modern bows which employ modifications of such limbs. Hence the energy at full draw is relatively lower in bows with straight limbs than in reflexed bows, or bows with backwardly curving tips or ears. It would appear, therefore, that with substantially higher energy content for the same maximum force, the bows which follow a modified Turkish design, or use backwardly curving tips, are to be preferred to bows with straight limbs. This is indeed true if they are as effective in transferring energy to the arrow.

Velocity-mass relations in arrows shot from a given bow.—An archer, as he gains experience with his bow, will notice—provided he shoots arrows of different weights—that the light arrow takes off with higher velocity than the heavier. This raises questions. First, can one establish a systematic relation between the mass of an arrow and the velocity imparted to it by a given bow? Second, can one find a relation between the mass of an arrow and the energy which is transferred to it from the bow? These two questions, and the search for their answers, lead to some other considerations of interest.

Figure 9 reproduces a mass-velocity curve obtained by plotting measured velocities of arrows of different masses against the mass values, all shot from a bow with given energy at full draw. The solid line is plotted from computed values of v and m, using the relation

$$E=\frac{mv^2}{2}+\frac{Kv^2}{2},$$

simplified to $E=\frac{1}{2}(m+K)v^2$.

The equation says that the energy E in the drawn bow is accounted for by the kinetic energy in the arrow, $\frac{1}{2}mv^2$, and another energy term, $\frac{1}{2}Kv^2$, which represents the part of E which failed to be transferred from the bow to the arrow; it is that part of the energy which is left behind when the arrow leaves the string. This term employs the same velocity v as that of the arrow, and a quantity K which has the dimensions of mass. This I have called the *virtual mass* of the bow.

A physical picture of virtual mass may be drawn as follows. Imagine the bow and string to have no mass, and imagine a mass K to ride "piggyback" on the arrow until the instant the arrow leaves the string. The velocity v is that which corresponds to kinetic energy equal to the energy E, transferred to a mass of $m+K$. The energy carried off by the arrow is $\frac{1}{2}mv^2$, which means that the energy left behind is $\frac{1}{2}Kv^2$. The virtual mass K has been found by many experi-



FIGURE 9.—Relation between mass of an arrow and its velocity when shot from a bow having 1,000 foot-poundals of available energy at full draw.

ments to be uniquely characteristic of the bow. In bows of high efficiency, i.e., of high energy transfer, K is small, and vice versa. The virtual mass of a longbow is large. It is much smaller in the "scientific" and the modern bows. This is the more readily understood when we consider that the limbs of a bow must themselves be accelerated by the stored energy in order to impart acceleration to the arrow. The long, heavy limbs of the longbow are sluggish as compared with the shorter and lighter limbs of its successors. Were it possible to transfer all the energy in the bow to the arrow, the virtual mass of the bow would be zero. Theoretically this might be achieved if a bow could be so designed that the limbs had zero velocity in the normal braced position at the instant of disengagement of the arrow. This is an unattainable ideal, but it has been approached to within 10 percent.

In closing this discussion, it is my hope that the purposes set forth at its beginning have been achieved. More detailed exposition of the many technical considerations involved in the design, construction



FIGURE 10.—A set of curves relating mass of an arrow to its velocity when shot from bows of different virtual mass but the same available energy.

and use of bows and arrows would far exceed its scope. The appended bibliography may serve as a guide for more thorough exploration of such technical matters as have been enumerated.

BIBLIOGRAPHY

(Abbreviations: S.A., Ye Sylvan Archer; A.R., Archery Review; A.B.R., American Bowman-Review)

CAVANAUGH, JAMES F.

1958. Standardization of procedures in bow testing. Archery, June.

ELMER, ROBERT P.

1933. Archery (rev. ed.), chap. 15.

1946. Target archery, pp. 184 et. seq.

ENGLISH, F. L.

1930. The exterior ballistics of the arrow. Journ. Franklin Inst., vol. 210, p. 805.

HICKMAN, C. N.

1929. Velocity and acceleration of arrows. Weight and efficiency of bows as affected by backing of bow. Journ. Franklin Inst., vol. 208, p. 521.

1930. Formulas for strains and stresses in a drawn bow. S.A., November.

1931a. A portable spark chronograph. Journ. Franklin Inst., vol. 211, p. 59.

HICKMAN, C. E.—Continued
1931b. Effect of rigid middle section on static strains and stresses. S.A., February.
1931c. Effect of bracing eight on static strains and stresses. S.A., March.
1931d. Effect of string weight on arrow velocity and efficiency of bows. S.A., April.
1931e. Effect of permanent set and reflexing on static strains and stresses. S.A., May.
1931f. Effect of bow length on static strains and stresses. S.A., August.
1931g. Effect of weight and air resistance of bow tips on cast. S.A., September.
1932a. Effect of thickness and width of a bow on its form in bending. S.A., January.
1932b. The neutral plane of bending in a bow. S.A., February.
1932c. Fiber stresses in bows. S.A., March.
1937. The dynamics of a bow and arrow. Journ. Appl. Phys., vol. 8, p. 404.
HICKMAN, C. N.; NAGLER, F.; and KLOPSTEG, P. E.
1947. Archery, the technical side (now out of print). Nat. Field Archery Assoc.
HIGGINS, GEORGE J.
1933. The aerodynamics of an arrow. Journ. Franklin Inst., vol. 216, p. 91.
KLOPSTEG, PAUL E.
1931. What is the proper cross section for a bow? S.A., December.
1932a. Analyzing the bow sight. S.A., January.
1932b. Constructing the bow with rectangular limb section. S.A., May.
1932c. The effect on scores of errors in aiming and holding. S.A., also A.R., June.
1932d. What of the bow? A.R., October.
1932e. The flight of an arrow. A.R., November.
1932f. A comparison of the point of aim and sight. A.R., July.
1933a. A study of points of aim. A.R., January.
1933b. Elements of the prism sight. A.R., February.
1933c. Photographing the paradox. A.R., April.
1933d. Some new light on the paradox of archery. December (and January 1934).
1934. Turkish archery and the composite bow. (Rev. ed., 1947.) (Both editions out of print.)
1935a. Getting the most out of the bowstave. A.R., June.
1935b. Science looks at archery. A monograph.
1939a. A graphic method of designing a bow. S.A., June.
1939b. The penetration of arrows. A.B.R., July.
1943a. Physics of bows and arrows. Amer. Journ. Phys., vol. 11, p. 175.
1943b. The whys and wherefores of cast. A.B.R., August.
1947. Archery. Encyclopedia Britannica, 14th ed. (1947 printing).
LOOMIS, A. L., and KLOPSTEG, PAUL E.
1920. The measurement of projectile velocity (Aberdeen Chronograph). Journ. AIEE, vol. 39, p. 98.
MCQUITTY, R. M.
1944. Aiming as affected by changes in velocity. A.B.R., June.
NAGLER, FORREST.
1933. Bow design. A.R., June and July.
1935. More about the elliptical bow. A.R., December (and January 1936).
NAGLER, F., and RHEINGANS, W. J.
1937. Spine and arrow design. A.B.R., June and July.

RHEINGANS, W. J.
1933. Debunking spine. A.R., May.
1934. Bow efficiency. A.R., February.
1936. Exterior and interior ballistics of bows and arrows. A.R., March and April.
RODGERS, W. L.
1935. The bow as a missile weapon. Army Ordnance, May–June.
SEAGRAVE, JOHN D.
1958. A survey of methods for measurement of arrow velocity. Archery, February.



Yours Truly
Horace A. Ford

An English longbow of the 1850's, like that of figures 1 and 2, at full draw. Reproduced from Horace A. Ford's "Archery in Theory and Practice," 1856. Ford was eleven times archery champion of England.



a, Modified grip of an American-made longbow to show the change in midsection from that of the English longbow. The midsection is made rigid, with "dips" where the limbs merge with the grip. b–d, A Turkish type composite bow (b) relaxed, (c) braced, and (d) at full draw. (From "Turkish Archery and the Composite Bow.")

a

b



c

A wood bow, of yew, made according to the design of figure 6, shown (a) relaxed, (b) braced, and (c) at full draw. The limbs are straight, and, when drawn, bend in circular arcs. Note how the slightly wavy grain in the wood has been followed by the bowyer, to avoid cutting across the grain. Note also that the limbs are of equal length (28″); the long (15″) rigid midsection; and the symmetry of the bent limbs relative to the position of the arrow.



a



b

A modern composite bow (bow of the 1960's) (a) relaxed, (b) braced, and pl. 5, at full draw. Note the length (ca. 20″) of the equal limbs, as compared with the 34″ length of the upper and 32″ lower limb of the English longbow of figure 1, and the rigid midsection, 27″ long, which is completely absent in the English longbow. (Photos courtesy of Bear

(See plate 4 for explanation.)